



Attn: Carlos Fornelli

September 8, 2017

Scope of work: Hard walls Rooms 204

We hereby wish to submit this proposal to furnish and install the following:

Class Room 204

- Remove white boards patch and prep damage plaster on walls for paint.
- Approx. 35Lf. X 10'6" ht.: 2 1/2" 20ga. metal studs framing, 5/8 drywall, tape finish ready for paint.
- Install 2ea. 3' X 7' Timely Frames, hard board doors, hinges, passage sets and door stops.
- Install 4" cove base (black)
- Install Y duct's to branch off existing air supply and route 2ea. new air grills in each room.
- Paint finish walls to match existing

Rm. 204

Grand Total \$19,379.00

Sincerely,

Stephen Muñoz